



# **Community Information Meeting**

#### Papakōlea Sewer Projects

November 18, 2021



## **Meeting Kuleana**

- 1) Be respectful of the person talking please do not interrupt the person that is talking;
- 2) Wait for the facilitator to call on you or type your question into the chat box
- 3) When addressing other participants (verbally or in the chat box), be respectful, show aloha, treat others how you would like to be treated;
- 4) Agree to disagree accept that others may have different perspectives and opinions.
- 5) Have an open mind take home new ideas or new information.



## **Meeting Agenda**

- To provide an update to the Papakolea Homestead Community on DHHL's Sewer Improvement Project
  - The purpose of the project is to upgrade sewer improvements and access which comply with City and County Standards.
- Question and Answer





#### **Phase – 1:**

\$13 Million Total Cost (2016-2019)

#### **Phase – 2:**

\$45 Million Total Cost (estimated)








# Papakolea Subdivision Phase 1 Sewer Improvements 2016-2019









#### **Sewer Line E & F:**

- 65 Lots
- 4,200 Linear feet
- 28 New sewer manholes







#### **Sewer Line E:**

Realigned and rerouted sewer line and manhole to avoid bisecting properties








#### **Sewer Line L Realignment:**

- 900 LF, 10-inch pipe
- 6 New sewer manholes
- 16 Lateral reconnections
- Abandon existing Sewer line K and L in place

#### **Completed:**

September 2019






#### **Slope C and C-1 Replacement:**

#### **Slope Stabilization**

- 34,000 square feet
- Completed June 2018
- Cost: \$4 Million

#### Sewer Line C & C-1

- Completed August 2019
- 520 Linear feet,
- 8" pipe
- (5) New sewer manholes





# Papakolea Subdivision Phase 2 Sewer Improvements 2020- present



## **Proposed Improvements**


#### **Objectives:**

- Replace aging sewer system (80+ years old)
- Reduce sewer spills
- To meet existing City & County of Honolulu Standards for ownership transfer
- Continue progress from Phase 1 sewer improvements projects



## Phase 2

- Phase 2A
  - Submitted Plans for City Review (May 2021)
- Phase 2B
  - Replace remaining gravity sewer lines and install low pressure sewer systems (LPSS).
- Sewer lines installed by pipe bursting or open trench.






## **Pipe Bursting**

#### **Static Pipe Bursting Process**

- A bursting head and new pipe is pulled through existing pipe
- Broken pipe is pushed into the surrounding soil
- Avoids exposing existing utilities
- Minimizes ground disturbance






## **Low Pressure Sewer System**

<u>Low Pressure Sewer</u> <u>System (LPSS)</u>

An alternative to a conventional gravity sewer system. Utilizes a collection tank and control panel to pump sewage from the house to the roadway sewer system.





# Phase 2A Scope of Work

#### Scope of Work

- Phase 2A
  - Replacement for Sewer Lines C, C-2, D, D-1, D-3, D-5 & G, and spot repairs using pipe bursting and open trench methods
  - CLSM fill and abandon 2,000 feet of pipe along SL K, L
  - Replace 3,400 feet of gravity sewer lines





## **Phase 2A Impacts**

#### **Typical Impacts**

- Remove trees and shrubs
- Relocate storage units/area, sheds, structures out of sewer easement.
- Demolish and reconstruct walls, fences, driveways, and sidewalks.
   Temporarily inaccessible during construction.





**Photos 1 & 2.** Reconstruct walkway and staircase between Auwaiolimu St. and laukea St.



# **Phase 2A Impacts**



**Photo 1.** Existing sewer line crosses under the existing historic drainage channel.



**Photo 2.** Exist. sewer line runs under a large existing mango tree. Tree to be potentially removed.



## **Phase 2B**

#### Scope of Work

- East of Tantalus Dr.
  - Replace Sewer Lines A, C, C-3, C-4, J
    - 2,120 feet of gravity sewer lines
  - Install 28 LPSS
    - SL D-2, D-4, I, & K-2 difficult accessibility
  - Upsize SL A south of laukea St. to 12-in.
  - Requires City & County of Honolulu coordination
- West of Tantalus Dr.
  - Alternative 1 All LPSS
  - Alternative 2 Partial LPSS & re-routing flows





#### Phase 2B — Alternative 1


#### West of Tantalus Dr.

- Keep same sewer flow path
- Convert 38 homes to LPSS
- 700 ft, 8-in gravity pipes
- 1,350 ft, 3-in sewer force mains
- CLSM fill and abandon 2,500 ft SL
  - Difficult accessibility and safety concerns. Structures built on SL A and along cliffside.

#### **Alternative #1:**

Estimated Cost: \$7.3 million








## Phase 2B – Alternative 2

- Connect to existing sewer system in Auwaiolimu St.
  - 8-inch 1,040 LF in Auwaiolimu St.
  - May require upgrades to City system downstream.

#### **Alternative #2:**

Estimated Cost: \$9.5 million





### Phase 2B – Alternate 2


#### West of Tantalus Dr.

- Convert 21 homes to LPSS
- 1,600 ft, 8-in gravity pipes
- 720 ft, 3-in sewer force mains
- CLSM fill and abandon 1,430 ft SL

#### **Alternative #2:**

Estimated Cost: \$9.5 million








# **Phase 2B Typical Impacts**

- LPSS requires coordination with homeowners for placement.
- Homeowners are responsible for management of pump station and laterals within property.
- Install sewer in access route from Hiilani St. to Auwaiolimu St.
- Coordinate with future city upgrades








## Phase 2B – Alternate 2 Impacts

- Heavy SHPD involvement
- Crosses the historic Auwaiolimu St. ditch
- Limited space to construct by ditch
- Auwaiolimu St. by contrary is sensitive area
  - Coordinate with City
    - A few unsewered homes along Auwaiolimu St. might need downstream upgrades



Key Map







## **Major Challenges**

#### **Construction**

- Accessibility (for construction & maintenance)
  - Majority of sewer lines are located:
    - Between homes
    - Behind buildings at top of steep drop offs
    - In sidewalks near retaining walls
  - Existing sewer easements need to be wider and .
     have been encroached.
  - Many obstacles near/atop line: homes, garages, large trees, retaining walls, etc.
  - Safety Sewer lines behind homes are typically at the top edge of steep slopes

#### **Coordination**

- Sewer Line replacement close coordination with homeowners for:
  - Access & impact to property
  - Clearing easements
  - LPSS Installation and acceptance of maintenance
- Heavy SHPD involvement with Phase 2B-Alt 2
  - Historical Ditch
  - Auwaiolimu St
- Coordination with City, their downstream system impacts Papakolea's



### Mahalo



DEPARTMENT OF HAWAIIAN HOME LANDS

www.dhhl.hawaii.gov/po/oahu